

AD-A107 408

TIPPETTS-ABBETT-MCCARTHY-STRATTON NEW YORK

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. KIRK LAKE DAM (INVENTORY NUMBER N.--ETC(U)


AUG 81 E O'BRIEN


DACW51-81-C-0008

NL

UNCLASSIFIED

1 of 5  
AD-A107 408





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD A107408

LOWER HUDSON RIVER BASIN

3  
LEVEL

KIRK LAKE DAM

PUTNAM COUNTY, NEW YORK  
INVENTORY NO. N.Y. 682

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

DOCUMENT IS BEST QUALITY PRACTICABLE.  
CONTAINED A  
NUMBER OF PAGES WHICH DO NOT  
IDENTIFY.



APPROVED FOR PUBLIC RELEASE;  
DISTRIBUTION UNLIMITED

NEW YORK DISTRICT CORPS OF ENGINEERS

SEPTEMBER 1981

DTIC  
ELECTE  
NOV 16 1981

S

D

FILE COPY  
DTIC

81

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A107408	
4. TITLE (and Subtitle) Phase I Inspection Report Kirk Lake Dam Lower Hudson River Basin, Putnam County, NY Inventory No. 682		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) EUGENE O'Brien		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Tippett-Abbott-McCarthy-Stratton The TAMS Building 655 Third Avenue New York, New York 10017		8. CONTRACT OR GRANT NUMBER(s) 15 DACW51-81-C-0008
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		12. REPORT DATE 13 August 1981
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
15. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)  National Dam Safety Program, Kirk Lake Dam (Inventory Number N.Y. 682), Lower Hudson River Basin, Putnam County, New York. Phase I Inspection Report.		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Kirk Lake Dam Putnam County Lower Hudson River Basin		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. The examination of documents and the visual inspection of Kirk Lake Dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the		

dam has some deficiencies which require further investigation and remedial action. ←

Using the Corps of Engineers screening criteria for the initial review of spillway adequacy, it has been determined that the dam would be overtopped for all storms exceeding approximately 6.1 percent of the Probable Maximum Flood (PMF). The spillway is therefore adjudged as "seriously inadequate" and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because of a "seriously inadequate" spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean, however, that based on an initial screening and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard for loss of life downstream from the dam.

The structural stability analysis based on available information and visual inspection indicates that the stability against sliding and overturning of the spillway section of the dam is inadequate.

The structural stability analysis based on available information and visual inspection indicates that the stability of the spillway section against sliding is inadequate for the following cases: Case II - normal loading with ice load, Case III - unusual loading 1/2 PMF and Case IV - extreme loading PMF. The stability of the spillway section against overturning is inadequate for Case II - normal loading with ice load, Case III - unusual loading, 1/2 PMF and Case IV - extreme loading, PMF.

DTIC  
ELECTE  
S NOV 16 1981 D  
D

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
F	230

**LOWER HUDSON RIVER BASIN**

**KIRK LAKE DAM**

**PUTNAM COUNTY, NEW YORK  
INVENTORY NO. N.Y. 682**

**PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**



**NEW YORK DISTRICT CORPS OF ENGINEERS**

**SEPTEMBER 1981**

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
KIRK LAKE DAM  
I.D. NO. N.Y. 682  
D.E.C. NO. 481  
LOWER HUDSON RIVER BASIN  
PUTNAM COUNTY, N.Y.

CONTENTS

	<u>Page No.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
a. Authority	1
b. Purpose of Inspection	1
1.2 DESCRIPTION OF THE PROJECT	1
a. Description of Dam and Appurtenant Structures	1
b. Location	2
c. Size Classification	2
d. Hazard Classification	2
e. Ownership	2
f. Purpose of Dam	2
g. Design and Construction History	2
h. Normal Operating Procedure	3
1.3 PERTINENT DATA	3
a. Drainage Area	3
b. Discharge at Dam Site	3
c. Elevation	3
d. Reservoir	3
e. Storage	3
f. Dam	4
g. Spillway	4
h. Reservoir Drain and Pipeline	4
2 ENGINEERING DATA	5
2.1 GEOLOGY	5



	<u>Page No.</u>
2.2 SUBSURFACE INVESTIGATIONS	5
2.3 DAM AND APPURTENANT STRUCTURES	5
2.4 CONSTRUCTION RECORDS	5
2.5 OPERATION RECORD	5
2.6 EVALUATION OF DATA	5
3 VISUAL INSPECTION	6
3.1 FINDINGS	6
a. General	6
b. Dam	6
c. Spillway	6
d. Outlets and Pipes	6
e. Abutments	7
f. Reservoir Area	7
3.2 EVALUATION OF OBSERVATIONS	7
4 OPERATION AND MAINTENANCE PROCEDURES	9
4.1 PROCEDURES	9
4.2 MAINTENANCE OF THE DAM	9
4.3 WARNING SYSTEM IN EFFECT	9
4.4 EVALUATION	9
5 HYDROLOGIC/HYDRAULIC	10
5.1 DRAINAGE AREA CHARACTERISTICS	10
5.2 ANALYSIS CRITERIA	10
5.3 SPILLWAY CAPACITY	10
5.4 RESERVOIR CAPACITY	11
5.5 FLOODS OF RECORD	11
5.6 OVERTOPPING POTENTIAL	11
5.7 EVALUATION	11

	<u>Page No.</u>
6     STRUCTURAL STABILITY	12
6.1   EVALUATION OF STRUCTURAL STABILITY	12
a.    Visual Observation	12
b.    Design and Construction Data	12
c.    Stability Analysis	12
7     ASSESSMENT/RECOMMENDATIONS	14
7.1   ASSESSMENT	14
a.    Safety	14
b.    Adequacy of Information	15
c.    Need for Additional Investigations	15
d.    Urgency	15
7.2   RECOMMENDED MEASURES	15

#### APPENDICES

A.    DRAWINGS
a.    Vicinity Map
b.    Topographic Map
c.    General Location Plan
d.    Spillway Plan and Sections
B.    PHOTOGRAPHS
C.    VISUAL INSPECTION CHECKLISTS
D.    HYDROLOGIC DATA AND COMPUTATIONS
E.    STABILITY ANALYSIS
F.    REFERENCES
G.    OTHER DATA

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

NAME OF DAM	Kirk Lake Dam, N.Y. 682
STATE LOCATED	New York
COUNTY LOCATED	Putnam
STREAM	Tributary of Muscoot River
BASIN	Lower Hudson
DATE OF INSPECTION	May 6, 1981

ASSESSMENT

The examination of documents and the visual inspection of Kirk Lake Dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies which require further investigation and remedial action.

Using the Corps of Engineers screening criteria for the initial review of spillway adequacy, it has been determined that the dam would be overtopped for all storms exceeding approximately 6.1 percent of the Probable Maximum Flood (PMF). The spillway is therefore adjudged as "seriously inadequate" and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because of a "seriously inadequate" spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean, however, that based on an initial screening and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard for loss of life downstream from the dam.

The structural stability analysis based on available information and visual inspection indicates that the stability against sliding and overturning of the spillway section of the dam is inadequate.

The structural stability analysis based on available information and visual inspection indicates that the stability of the spillway section against sliding is inadequate for the following cases: Case II - normal loading with ice load, Case III - unusual loading 1/2 PMF and Case IV - extreme loading PMF. The stability of the spillway section against overturning is inadequate for Case II - normal loading with ice load, Case III - unusual loading, 1/2 PMF and Case IV - extreme loading, PMF.


It is therefore recommended that within 3 months of notification to the owner, a detailed hydrological and hydraulic investigation be undertaken to more accurately determine the site specific characteristics of the watershed and their affect upon the overtopping potential of the dam. At the same time, a structural stability study of the spillway section should be performed as detailed in Section 6.1c. Within twelve (12) months of the date of notification to the owner, any modification to the structure deemed necessary as a result of investigations, to achieve a spillway capacity adequate to discharge the outflow from at least one-half (1/2) PMF, should have been completed. In the interim, a detailed emergency action plan and warning system should be promptly developed. Also, during periods of unusually heavy precipitation, around-the-clock surveillance should be provided.

In addition, the dam has a number of problem areas which, if left uncorrected, have the potential for the development of hazardous conditions and must be corrected within twelve (12) months.

The following are the recommended measures which must be corrected:


- 1) All debris should be cleaned out from the downstream channel and hauled away. The collapsed section of the downstream channel should be cleared and repaired.

- 2) The small saddle near the right abutment contact should be filled in.
- 3) Stones missing in the masonry spillway section should be replaced.
- 4) All moving parts of the gate system should be lubricated.
- 5) Provide a program of periodic inspection and maintenance of the dam and appurtenances including yearly operation and lubrication of the reservoir drainage system. Document this information for future reference. The emergency action plan described in Section 7.1d should be developed and updated periodically during the life of the structure.



Eugene O'Brien, P.E.  
New York No. 29823

Approved by:



Col. W. M. Smith Jr.  
New York District Engineer

Date:

19 AUG 1981



1. OVERVIEW

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM  
KIRK LAKE DAM  
I. D. NO. N.Y. 682  
D.E.C. No. 481  
LOWER HUDSON RIVER BASIN  
PUTNAM COUNTY, N.Y.

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers by Contract No. DACW 651-81-C-008 dated 14 December 1980 in fulfillment of the requirements of the National Dam Inspection Act, Public Law 92-367, 8 August 1972.

b. Purpose of Inspection

The inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF THE PROJECT

a. Description of the Dam and Appurtenant Structures

The Kirk Lake Dam is composed of an approximately 220 foot long stone masonry-earth buttress dam. The crest of the dam is 60 feet wide and its maximum height above the river is 28 feet. The downstream masonry wall face of the dam is vertical. Upstream of the 11 foot thick wall is a 50 foot wide earth embankment with a slight upstream slope. Upstream of the earth embankment is another smaller concrete masonry wall. The slope of the fill upstream of this wall is unknown.

Centrally located within the dam is a 15.5 foot wide stone masonry spillway section which has a 6 feet by 4 feet chamber.

The spillway has sills at three levels and the maximum and minimum depths of the sills are 5.3 feet and 2.3 feet respectively from the top of the dam. At the bottom of the chamber is the control for the reservoir drain. The reservoir drain is a 36-inch cast iron pipe, controlled by a gate valve. The intake is located in the lake approximately 200 feet upstream of the dam. The outlet is in the base of the spillway structure.

The spillway and reservoir drains discharge through a stone masonry lined channel about 15 feet deep.

b. Location

Kirk Lake Dam is located on a tributary of the Muscoot River about 1/2 mile northeast of the village of Mahopac Falls in Putnam County, New York. The dam is about 1/3 mile north of Route 6N near its intersection with Hill Street.

c. Size Classification

The dam is 28 feet high and has a reservoir with a maximum storage capacity of 1,822 acre-feet and therefore is classified as an intermediate dam (storage capacity  $> 1,000$  acre-feet,  $< 50,000$  acre-feet).

d. Hazard Classification

The dam is in the "high" hazard potential category because of its close proximity to the village of Mahopac Falls.

e. Ownership

Kirk Lake Dam is owned by the New York City Bureau of Water Supply. The person to contact is Mr. Don Grassman at the Department of Environmental Protection, P.O. Box 66, Valhalla, New York, 10595, Telephone (914) 232-5711.

f. Purpose of Dam

The dam impounds water for a recreational lake.

g. Design and Construction History

The dam was designed and built in 1871 and major reconstruction was done in 1881. The designers and constructors are not known.



h. Normal Operating Procedures

Operations are carried out on an as-needed basis, with the water level maintained at between 1 and 3 feet below the lowest spillway sill. The 36 inch cast iron pipe serves as reservoir drain. The intake of the drain is about 200 ft from the upstream face.

1.3 PERINENT DATA

a.	<u>Drainage Area</u> , Square Miles	2.95
b.	<u>Discharge at Dam Site</u> , cfs	
	Ungated Spillway	279
	Maximum Capacity - 36-Inch Cast Iron Pipe	160
	Total Discharge Maximum Pool	439
c.	<u>Elevation</u> , Feet Above MSL,	
	USGS Datum	
	Top of Dam	592.3
	Maximum Pool	592.3
	Spillway Crest - Lowest Sill	587.0
	Spillway Crest - Mid Sill	589.0
	Spillway Crest - High Sill	590.3
	Invert Low Level Intake	Unknown
	Invert Low Level Outlet	568.3
d.	<u>Reservoir</u>	
	Length of Normal Pool (miles)	0.8
	Surface Area of Maximum Pool (Acres)	216
	Surface Area of Normal Pool (Acres)	124
e.	<u>Storage</u> , Acre-feet	
	Reservoir at Spillway Crest	920
	Reservoir at Maximum Pool	1822

f. Dam

Type	Masonry Wall with Upstream Earth Embankment
Length (feet)	220
Upstream Slope	Unknown
Downstream Slope	Vertical
Crest Elevation	592.3
Crest Width	61 feet
Grout Curtain	Unknown
Cutoff	Unknown

g. Spillway

Type	Uncontrolled Broad Crested Weir
Size	15 feet wide
Crest Elevations - Low Sill	587
Mid Sill	589
High Sill	590.3
Upstream Channel	Concrete Slab with Masonry Concrete Training Walls
Downstream Channel	Masonry Walled Channel - 15 feet wide base approx- imately 4V to 1H sloped walls

h. Reservoir Drain and Pipeline

Upstream. The intake for the 36-inch cast iron reservoir drain line is located about 200 feet upstream of the dam. A gate valve, located in a chamber below the spillway, controls discharges. The outlet is located in the base of the spillway section of the dam.

## SECTION 2 - ENGINEERING DATA

### 2.1 GEOLOGY

The records of the owner contain no data on site geology. However, there is data available in the literature on the general geology of the area. Kirk Lake Dam is located in the Hudson Highlands section of the New England Uplands physiographic province. The province is characterized by a low, but rugged mountain range consisting primarily of igneous and metamorphic rock. The rock underlying the area of Kirk Lake is Precambrian biotite-quartz-plagioclase paragneiss with subordinate biotite granitic gneiss, amphibolite and calcilicate rock.

### 2.2 SUBSURFACE INVESTIGATIONS

There are no records of subsurface investigations carried out at the site. It is known that the surficial soils in the vicinity of the Kirk Lake Dam are coarse grained glacial till material.

### 2.3 DAM AND APPURTENANT STRUCTURES

There are no records or drawings available with regard to the original construction of the dam in 1872. No records are available of the reconstruction carried out in 1881. There is some information regarding the dam section shown in the inspection reports of 1915 which are included in Appendix

### 2.4 CONSTRUCTION RECORDS

No information has been located in relation to the construction of the project. The name(s) of the contractor(s) is (are) unknown.

### 2.5 OPERATION RECORDS

There is no regularly scheduled operation of the dam. The outlets are operated on an as-needed basis to maintain a water level between 1 and 3 feet below the lowest sill of the spillway. Maintenance is performed on an as-needed basis by staff of the owner. No systematic monitoring of the dam is in effect.

### 2.6 EVALUATION OF DATA

There is sufficient data available to support a Phase I evaluation of the dam.

## SECTION 3 - VISUAL INSPECTION

### 3.1 FINDINGS

#### a. General

The visual inspection of Kirk Lake Dam was made on May 6, 1981. The weather was clear and the temperature was in the mid 60's. At the time of the inspection, the water level in the reservoir was about 1 foot below lowest sill of the spillway.

#### b. Dam

The stone masonry and earth buttress portions of the dam appears to be in good condition. The vertical and horizontal alignment of the crest appears to be good (see Photos 2 and 3).

The visible portion of the upstream face of the dam is in good condition with some minor ice damage to the upstream wall.

The downstream face of the masonry wall is in good condition except minor vegetation growing through.

There is no emergency action plan for the project.

#### c. Spillway

The masonry spillway is in good condition. There are a few stones missing in the central portion of the spillway. The approach channel of the spillway is clear and training walls are in good condition except for some local ice damage. The tailrace channel of the spillway is choked with heavy debris and a section of channel wall about 300 feet downstream of the dam (see Photos 5 and 10) is collapsed.

#### d. Outlets and Pipes

The condition of the reservoir drain and in and intake could not be determined because it was unobservable. The control for the gate valve is in good operating condition but requires lubrication. The 36-inch reservoir drain pipeline was unobservable. The outlet of the pipe appears to be in good condition. The discharge was free of sediment or rust staining (see Photo 7) and therefore the condition of the reservoir drain could not be determined.

e. Abutments

The abutment contact and abutment at the left end of the dam are in good condition. The right abutment is in good condition, however, a small "ditch" passes over the contact. The ditch is slightly lower than crest and at the time contained some standing water (see Photo 11 ).

f. Reservoir Area

The reservoir area is hilly and for the most part, developed with small homes. There is some forested area surrounding the reservoir and the area to the north is marshy land. There are neither slides, rockfalls or sloughing around the reservoir.

3.2 EVALUATION OF OBSERVATIONS

Visual observations made during the course of the inspection did not indicate any serious problems which would adversely affect the adequacy of the dam and appurtenant facilities. The following is a list in order of importance of problem areas encountered which should be corrected before further deterioration results in the development of a hazardous condition. Appropriate remedies are also included.

1) The downstream channel for the spillway and reservoir drain is filled with debris, and a section of the channel wall has collapsed resulting in the clogging of the channel. The debris should be removed and hauled away and the collapsed section of the channel should be repaired.

2) The small drainage ditch which is near the right abutment contact is subject to flow conditions during high water. This ditch should be filled in with properly compacted earth to an elevation equal to the crest elevation of the dam.

3) Stones have been pried loose in the spillway. These stones should be replaced. Additionally, concrete damaged by ice in the approach channel should be repaired.

4) All moving parts of the outlet system should be lubricated.

5) A program of periodic inspection and maintenance of the dam and appurtenances, should be provided including yearly

lubrication of the moving parts of the outlet system. The inspection and the test operations should be documented for future reference. The emergency action plan described in Section 7.1d should be maintained and updated during the life of the project.

## SECTION 4 - OPERATION AND MAINTENANCE PROCEDURES

### 4.1 PROCEDURES

No written operation and maintenance procedure manuals exist for the project. Normal operation of the project consists of maintaining a reservoir level about 1 to 3 feet below lowest sill of the spillway by releasing the discharge through the reservoir drain.

### 4.2 MAINTENANCE OF THE DAM

There is no regular maintenance schedule for the dam. Maintenance and repairs which are required are carried out by the staff of the owner under the direction of Mr. Birrel, Assistant Civil Engineer for the Bureau of Water Supply.

### 4.3 WARNING SYSTEM IN EFFECT

No warning system is in effect or in preparation.

### 4.4 EVALUATION

The overall maintenance of the Kirk Lake Dam is considered inadequate in the following areas.

- 1) The downstream channel for the spillway and outlet needs to be cleaned out.
- 2) Moving parts of the outlet works require lubrication.
- 3) Vegetation, although minor, at the downstream face of the dam, should be removed.

## SECTION 5 - HYDROLOGIC/HYDRAULIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

The Kirk Lake Dam is located on an unnamed tributary of the Muscoot River about 1/2 mile north of Mahopac Falls, Carmel Township, Putnam County. The Hydrologic Unit Code number for this area is 02030101. The drainage basin extends north of the lake with an area of 2.95 square miles. The basin consists of a north/south valley with approximately 15 percent swamp area in the middle and steep slopes at the edges. About 30 percent of the basin is suburban with the remaining 70 percent being wooded slopes.

### 5.2 ANALYSIS CRITERIA

The analysis of the adequacy of the spillway was performed by developing a design flood, using the unit hydrograph method and the Probable Maximum Precipitation (PMP). The all season 200 square mile 24 hours PMP for the Carmel area is 22 inches (Weather Bureau sources). The unit hydrograph was computed by the Snyder method using coefficient of 2 and 0.625 for  $C_t$  and  $C_p$ , respectively. The inflow hydrograph was developed by the U.S. Army Corps of Engineers HEC-1DB computer program. Initial loss of 1.0 inch and constant loss of 0.1 inch/hour were estimated as representative of the basin for the design storm.

In accordance with the Recommended Guidelines for Safety Inspection of Dams (Ref. 3 ), the adequacy of the spillway was analyzed using the Probable Maximum Flood (PMF). A multi-ratio analysis was performed for the full, 0.75, 0.50 and 0.25 PMF.

### 5.3 SPILLWAY CAPACITY

The spillway, which is centrally located in the dam, is a 15.5 feet wide stone masonry structure. The spillway has broad crested overflow sills at several different heights. The maximum and minimum depths of the sills are 5.3 feet and 2.3 feet from the top of the dam respectively. The computed maximum discharge over the sills with the water surface at El 592.3 (top of dam) is 309.7 cfs.



#### 5.4 RESERVOIR CAPACITY

The normal reservoir capacity is listed as 920 acre-feet. The computed surcharge storage of 901.7 acre-feet, while water level reaches the top of the dam (592.3 feet MSL), is equivalent to approximately 5.7 inches of runoff over the entire basin.

#### 5.5 FLOODS OF RECORD

There are no records available of floods or maximum lake elevation.

#### 5.6 OVERTOPPING POTENTIAL

The potential of the dam being overtopped was investigated on the basis of the spillway discharge capacity and the available surcharge storage to meet the selected design flood inflows.

The analysis was performed assuming that the reservoir level was at the lowest sill of the spillway at the start of the flood event.

<u>Ratio of PMF</u>	<u>Inflow Peak (cfs)</u>	<u>Overtopping (ft)</u>	<u>Outflow Peak (cfs)</u>
1.00	8006	3.56	5070
0.75	6004	2.65	3401
0.50	4003	1.37	1496
0.25	2001	0.00	217

The analysis indicates that the spillway is capable of passing 6.1 percent of the PMF without overtopping the dam.

#### 5.7 EVALUATION

The spillway at Kirk Lake Dam does not have sufficient spillway capacity to pass either the PMF or one-half (1/2) PMF without overtopping the dam. The overtopping of the dam could cause the failure of the dam, thus significantly increasing the hazard for the loss of life downstream. The spillway is therefore assessed as being "seriously inadequate" and the dam is assessed as unsafe, non-emergency.

## SECTION 6 - STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

Visual observations did not indicate any structural problems with the embankment or appurtenant structures with the reservoir at its present level. There are no observable adverse conditions which would affect the stability of the dam at the present time.

#### b. Design and Construction Data

There are no design calculations or construction data available.

On the basis of performance, visual inspection, as well as engineering judgment, the embankment and appurtenant structures appear to be adequate with the reservoir at its present level.

#### c. Stability Analysis

As there were no drawings available, the structural stability of the masonry spillway section was analyzed based on an assumed typical section and field measurements. Stability analysis for the spillway section was done in accordance with the Corps of Engineers Recommended Guidelines. (Reference 3). The following table shows the loading cases considered and the results of the analysis.

<u>Loading Case</u>	<u>Overturning (see Appendix E)</u>	<u>Sliding factor of Safety (see Appendix E)</u>
I) Normal Loading Condition with reservoir at Spillway Crest, No Ice Load	Inside of Middle 1/3	3.41
II) Normal Loading Condition with Reservoir at Spillway Crest, with Ice Load	0.63 ft. Outside of Middle 1/3	2.20

<u>Loading Case</u>	<u>Overturning (see Appendix E)</u>	<u>Sliding Factor of Safety (see Appendix E)</u>
III) Unusual Loading, One-Half (1/2) PMF, water overtopping the dam by 1.18 feet	0.75 ft. Outside of Middle 1/3	1.68
IV) Extreme Loading: PMF-water overtopping the dam by 3.29 feet	1.75 ft. Outside of Middle 1/3	1.40
V) Unusual Loading; Reservoir level of spillway crest, 0.05 g earthquake force	Inside of Base	2.52

The structural stability analysis based on available information and visual inspection indicates that the stability of the spillway section against sliding is inadequate for the following cases: Case II - normal loading with ice load, Case III - unusual loading 1/2 PMF and Case IV - extreme loading PMF. The stability of the spillway section against overturning is inadequate for Case II - normal loading with ice load Case III - unusual loading, 1/2 PMF and Case IV - extreme loading PMF.

Since exact geometry of the spillway section, foundation conditions, upstream backfill characteristics and extent, as well as the extent and magnitude of the uplift pressure are unknown, it is recommended that a more detailed structural stability study be performed. The study should include field investigations to obtain more information regarding the extent and characteristics of the backfill and foundation materials, as well as the quality and condition of the observable masonry of the structure. Based on the results of the analysis, modifications to the spillway should be recommended.

## SECTION 7 - ASSESSMENT/RECOMMENDATIONS

### 7.1 ASSESSMENT

#### a. Safety

Examination of the available documents and visual inspections of the Kirk Lake Dam and appurtenant structures did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies which require further investigation and remedial action.

Using the Corps of Engineers screening criteria for review of spillway adequacy, it has been determined that the dam would be overtopped for all storms exceeding approximately 35 percent of the PMF. The overtopping of the dam could cause the erosion of both abutments, resulting in dam failure, thus significantly increasing the hazard for loss of life downstream. The spillway is therefore adjudged as "seriously inadequate" and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because of a "seriously inadequate" spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean, however, that based on an initial screening and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard to loss of life downstream from the dam.

The structural stability analysis based on available information and visual inspection indicates that the stability of the spillway section against sliding is inadequate for the following cases: Case II - normal loading with ice load, Case III - unusual loading 1/2 PMF and Case IV - extreme loading PMF. The stability of the spillway section against overturning is inadequate for Case II - normal loading with ice load, Case III - unusual loading, 1/2 PMF and Case IV - extreme loading PMF.

b. Adequacy of Information

The information and data available were adequate for the performance of a Phase I inspection, except as noted in Sections 6.1c and 6.1d.

c. Need for Additional Investigations

Since the spillway is considered to be "seriously inadequate", additional hydrologic/hydraulic investigations are required to more accurately determine the site specific characteristics of the watershed. After the in-depth hydrologic/hydraulic investigations have been completed, remedial measures must be initiated to provide spillway capacity sufficient to discharge the outlet from the one-half (1/2) PMF event. In addition, an investigation of the structural stability of the spillway portion of the dam is required.

d. Urgency

The additional hydrologic/hydraulic investigations and the stability investigation which are required must be initiated within 3 months from the date of notification. Within 18 months of notification, remedial measures determined as a result of these investigations must be initiated, with completion of these measures during the following year. In the interim, develop an emergency action plan for the notification of downstream residents and proper government authorities in the event of overtopping and provide around-the-clock surveillance of the dam during periods of extreme runoff. The other problem areas listed below must be corrected within one year from notification.

7.2 RECOMMENDED MEASURES

The following are the recommended measures.


- 1) The results of the aforementioned investigation will determine the appropriate remedial measures required regarding spillway.
- 2) All debris should be cleaned out of the downstream channel and hauled away. The collapsed section of the downstream channel should be cleared out and repaired.

- 3) The small saddle near the right abutment contact should be filled in with properly compacted earth.
- 4) Stones missing in the spillway section should be replaced.
- 5) A program of periodic inspection and maintenance of the dam and appurtenances should be provided including yearly operation and lubrication of the repaired gates. The emergency action plan described in Section 7.1b should be maintained and updated periodically during the life of the structure. The inspection and the test operation should be documented for future reference.

DRAWINGS

- a. Vicinity Map
- b. Topographic Map
- c. General Location Plan (DRAW # 1)
- d. Spillway Plan and Sections (DRAW # 2)



APPENDIX A




Scale: 1"=2.2 Miles

KIRK LAKE DAM  
VICINITY MAP





LAKE CARMEL, N.Y. AND OSCAWANA LAKE, N.Y.  
 QUAD TOPOGRAPHIC MAP  
 KIRK LAKE DAM




PLAN - KIRK LAKE DAM


SCALE: 1" = 50'

NOTES:


- i) For Details of Spillway See Drawing No. 2
- ii) All dimensions from field measurements.



PLAN  
SCALE: 1" = 5'



SECTION A-A  
SCALE 1" = 5'



SECTION B-B  
SCALE: 1" = 5'

# SPILLWAY - PLAN & SECTIONS KIRK LAKE DAM

DWG #2


2

PHOTOGRAPHS

APPENDIX B



2. VIEW ALONG CREST OF DAM FROM THE  
RIGHT ABUTMENT.




3. VIEW ALONG CREST OF DAM FROM  
LEFT ABUTMENT.




4. VIEW OF SPILLWAY APPROACH CHANNEL



5. VIEW OF TERRACE CHANNEL



6. CONTROL FOR  
LOW LEVEL  
OUTLET



7. CLOSEUP OF LOW LEVEL OUTLET






8. UPSTREAM VIEW OF SPILLWAY



9. DOWNSTREAM VIEW OF SPILLWAY



10. VIEW OF COLLAPSED PORTION OF TAILRACE CHANNEL



11. VIEW OF LOW SADDLE NEAR RIGHT ABUTMENT CONTACT.

VISUAL INSPECTION CHECKLISTS

APPENDIX C

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam Kirk Lake Dam  
Fed. I.D. # NY 682 DEC Dam No. 481  
River Basin Lower Hudson  
Location: Town Carmel County Putnam  
Stream Name Muscoot River  
Tributary of Muscoot River  
Latitude (N) 41-22.7 Longitude (W) 73-45.5  
Type of Dam Masonry with earth fill upstream  
Hazard Category High  
Date(s) of Inspection May 6 1981  
Weather Conditions FAIR 65°F  
Reservoir Level at Time of Inspection 1.5 below spillway crest

b. Inspection Personnel K Szalay, J Fiteni JR.

c. Persons Contacted (Including Address & Phone No.) Mr. C. Picha, (914) 232-5171  
NYC Dept. of Env. Protection, PO Box 66 Valhalla, N.Y. 10595  
MR. Birrell - (914) 225-3550.

d. History:

Date Constructed 1871 Date(s) Reconstructed 1881

Designer Unknown

Constructed By Unknown

Owner NYC Dept. of Env. Conservation

(4) Slope Protection Concrete Wall - good  
condition

(5) Surface Cracks or Movement at Toe None

d. Downstream Slope

(1) Slope (Estimate - V:H) Vertical Masonry Wall

(2) Undesirable Growth or Debris, Animal Burrows None

(3) Sloughing, Subsidence or Depressions None

(4) Surface Cracks or Movement at Toe None

(5) Seepage None

(6) External Drainage System (Ditches, Trenches; Blanket) None

(7) Condition Around Outlet Structure Structure in good con-  
dition, channel debris clogged

(8) Seepage Beyond Toe None

e. Abutments - Embankment Contact

Left abutment - good

Right abutment - small depression below crest level.

(1) Erosion at Contact None

(2) Seepage Along Contact Evidence of possible past seepage in right abutment contact at higher reservoir levels

3) Drainage System

a. Description of System one 36 inch  $\phi$  cast iron low level outlet pipe. Controlled from well in middle of spillway by slide gate. Intake located about 400' out in lake. Control by multigear wheel

b. Condition of System good operating condition

c. Discharge from Drainage System regulated by Mr. Birrel - Discharging at time of visit. Usual condition is to discharge controlled amounts.

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.)

None

5) Reservoir

- a. Slopes Hilly - some development - Generally  
Glacial Till material - Stable
- b. Sedimentation Some minor amounts
- c. Unusual Conditions Which Affect Dam None

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) Few homes (10)  
downstream, Highway 6N about 1/4 mile d/s
- b. Seepage, Unusual Growth None obvious
- c. Evidence of Movement Beyond Toe of Dam None
- d. Condition of Downstream Channel Downstream channel is paved  
Much debris, one collapsed section

7) Spillway(s) (Including Discharge Conveyance Channel)

- Multi-levelled structure approximately in  
center of dam, Masonry walls and bottom
- a. General good condition, few stones missing  
due to recent vandalism, approach channel  
clear, some ice damage to training walls.  
Downstream channel good but clogged by debris.
- b. Condition of Service Spillway good condition  
few stones missing

c. Condition of Auxiliary Spillway None

d. Condition of Discharge Conveyance Channel Channel is  
Clogged by debris, natural as well as  
dumped. Stone paved channel has  
collapsed at one section about 400' D/S  
of dam.

3) Reservoir Drain/Outlet

Type: Pipe ☒ Conduit \_\_\_\_\_ Other \_\_\_\_\_

Material: Concrete \_\_\_\_\_ Metal ☒ Other \_\_\_\_\_

Size: 36" Length ≈ 400'

Invert Elevations: Entrance unknown Exit 560

Physical Condition (Describe): UNKNOWN Unobservable ☒

Material: \_\_\_\_\_

Joints: \_\_\_\_\_ Alignment \_\_\_\_\_

Structural Integrity: \_\_\_\_\_

Hydraulic Capability: \_\_\_\_\_

Means of Control: Gate ☒ Valve \_\_\_\_\_ Uncontrolled \_\_\_\_\_

Operation: Operable ☒ Inoperable \_\_\_\_\_ Other \_\_\_\_\_

Present Condition (Describe): good - needs lubrication



9) Structural

- a. Concrete Surfaces Masonry Surfaces are  
in generally good condition. Few missing  
blocks
- b. Structural Cracking None Visible
- c. Movement - Horizontal & Vertical Alignment (Settlement) None  
Visible or evident
- d. Junctions with Abutments or Embankments Good condition
- e. Drains - Foundation, Joint, Face None
- f. Water Passages, Conduits, Sluices None
- g. Seepage or Leakage None Visible

- h. Joints - Construction, etc. Masonry joints in good condition, repaired as required
- i. Foundation No evidence of or visible problems
- j. Abutments good condition
- k. Control Gates good operating condition (see items)
- l. Approach & Outlet Channels Approach channel wall - some concrete deterioration - otherwise ok. outlet channel - good condition except one section collapsed  $\approx$  300 ft downstream, debris throughout
- m. Energy Dissipators (Plunge Pool, etc.) None
- n. Intake Structures Not visible
- o. Stability Visually ok - To be calculated
- p. Miscellaneous \_\_\_\_\_

HYDROLOGIC DATA AND COMPUTATIONS

APPENDIX D

## CREST:

ELEVATION: 592Type: Masonry WallsWidth: 11 FeetLength: 205Spillover Masonry Structure - 15.5 Feet wide - SteppedLocation Near Center of DAM

## SPILLWAY:

## SERVICE

## AUXILIARY

Varies 587 → 590

Elevation

Masonry - Broad Crested

Type

15.5 feet

Width

Type of Control

Uncontrolled

Controlled:

Type

(Flashboards; gate)

Number

Size/Length

Invert Material

Anticipated Length  
of operating service≈ 100 feet

Chute Length

Slopes 4/5 ≈ 3 feet  
beyond that un-  
observableHeight Between Spillway Crest  
& Approach Channel Invert  
(Weir Flow)

HYDROMETEROLOGICAL GAGES:

Type : None Used

Location: \_\_\_\_\_

Records:

Date - \_\_\_\_\_

Max. Reading - \_\_\_\_\_

FLOOD WATER CONTROL SYSTEM:

Warning System: None

Method of Controlled Releases (mechanisms):

\_\_\_\_\_  
\_\_\_\_\_

DRAINAGE AREA: 2.95 sq. miles

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: Rural

Terrain - Relief: Hilly

Surface - Soil: Glacial Till

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

Potential Sedimentation problem areas (natural or man-made; present or future)

None

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

None

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the  
Reservoir perimeter:

Location: None

Elevation: \_\_\_\_\_

Reservoir:

Length @ Maximum Pool 0.8 (Miles)

Length of Shoreline (@ Spillway Crest) 3.1 (Miles)

# TAMS

Job No. 1579-13

Project KIRK LAKE DAM.

Subject \_\_\_\_\_

Sheet 1 of \_\_\_\_\_

Date JAN 21, 1981

By D.L.C.

Ch'k. by \_\_\_\_\_

LAKE EL.

587' MSL

LAKE PERIMETER

0.25" / 16,500' / 3.13 mi.

FETCH

4000'

LAKE AREA

4236

1.31

4105

1.35

123.47 ac

1057

1.39

0918

Drainage Area

5800

20.69

3731

20.59

1890.73 / 2.95 mi<sup>2</sup>

4105

20.49

2056

600 FT CONTOUR

.6582

3.79

.6203

3.815.

350.32 ac

3.82

.5521

620 FT CONTOUR

# TAMS

Job No. 1579-13

Sheet 2 of       

Project KIRK LAKE DAM

Date 1/81

Subject 600 CONTOUR LINE AREA

By A. PERDOMO

Ch'k. by       

## PLAN. RDNG

		<u>Sq. INC.</u>	<u>ACRES</u>	<u>Sq. MILES</u>
4235	>	3.70		
3865				
	>	3.71	340.6	0.532
4606	>	3.71		
4235				



# TAMS

Job No. 1579-04

Sheet 3 of     

Project KIRK LAKE

Date 7-20-91

Subject HYDROLOGIC / HYDRAULIC COMPUTATION

By D.L.C.

Ch'k. by     

EL	H	H <sub>1</sub>	L <sub>1</sub>	Q <sub>1</sub>	H <sub>2</sub>	L <sub>2</sub>	Q <sub>2</sub>	H <sub>3</sub>	L <sub>3</sub>	Q <sub>3</sub>	Q <sub>TOTAL</sub>
587	0										0
588	1		6.8	18.0							18.0
589	2		"	50.8	0						50.8
590	3		"	93.3	1	1.6	4.2	0		0	97.5
591	4		"	143.6	2	"	11.9	1	7.1	18.7	174.2
592.3	5.3		"	219.0	3.3	"	25.3	2.3	"	65.4	309.7
594	7		"	332.5	5.	"	47.2	4	"	150.0	529.7
597	10.		"	567.7	8	"	95.6	7	"	347.1	1010.4

USE  $C = 2.64$

LOW LEVEL OUTLET IS ASSUMED CLOSED FOR PMF ANALYSIS

EL	$\Delta H$	AREA	MEAN AREA	$\Delta VOL$	SURCHARGE STORAGE
Fr	(Ft)	(Ac)	(Ac)	(Ac Ft)	(Ac Ft)
587		124			0
	3		150.1	450.3	
590		176.2			450.3
	2.3		196.25	451.4	
592.3		216.3			901.7
	2.7		239.8	647.5	
595		263.3			1549.2
	5.0		306.8	1534.0	
600		350.3			3083.2

# TAMS

Job No. 1579  
 Project KIRK LAKE DAM INSPECTION  
 Subject HYDROLOGIC/HYDRAULIC COMPUTATIONS

Sheet 4 of         
 Date MAY 18 1981  
 By D. L. C  
 Ch'k. by       

FROM HYDROMET #33

ALL SEASON 200 SQ MILE 24 hour PMP = 22 inches

DURATION  
IN HOURS

Percent of  
INDEX RAINFALL

6 112

12 123

24 133

48 141

Assume INITIAL LOSS  $\approx 1.0$  inches

$\frac{1}{4}$  CONSTANT LOSS  $\approx 0.1$  inch/hour

% Impervious area 0.1

Assume SNYDER COEFS  $C_p \approx 0.625$  &  $640 C_p = 400$

$\frac{1}{4}$   $C_T \approx 2.0$

$L = 3.75'' = 7500' \approx 1.4$  mi

$L_{CN} = 0.9'' = 1800' \approx 0.34$  mi

$t_p = C_T (L L_{CN})^{0.3} = 2 (1.4 \times 0.34)^{0.3} = 1.6$  hours

$t_n = t_p / 5.5 = 1.6 / 5.5 = 0.29$  hrs use  $t_R = 0.5$  hrs

$t_{PR} = t_p + 0.25(t_R - t_n) = 1.6 + 0.25(0.5 - 0.29)$   
 $= 1.6 + 0.05 = 1.65$  hours

# TAMS

Job No. 1579-13

Project KIRK LAKE

Subject HYDROLOGIC/HYDRAULIC COMPUTATIONS

Sheet 5 of     

Date 5/20/81

By D.K. BORAH

Ch'k. by     

Basin area = 2.95 sq. miles

Water Surface area:

Lake = 0.194 sq. miles

Swamps etc. = 0.155

Total = 0.299 sq. miles


Ratio of water surface area to total basin area =  $\frac{0.299}{2.95} = 0.101$   
 $\approx 0.1$

D/s ch. and characteristics

Length = 1000 ft.

Slope =  $\frac{1}{1000} = 0.001$

Cross section:





11/16/80

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT 1  
ROUTE HYDROGRAPH TO 2  
ROUTE HYDROGRAPH TO 3  
END OF NETWORK

Sheet 7 of 21

.....  
FLOOD HYDROGRAPH PACKAGE (FHEC-1)  
DAP SAFETY VERSION JULY 1978  
LAST MODIFICATION 01 APR 80  
.....

RUN DATE: 81/07/21  
TIME: 12.35.33

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80  
 \*\*\*\*\*

RUN DATE: 81/07/21.  
 TIME: 12:35:53.

KIRK LAKE DAM  
 PHASE 1 INSPECTION  
 HEC-10B PMF ANALYSIS MAY 81

JOB SPECIFICATION  
 HQ NHR NMIN IDAY IHR IMIN METRC IPLY IPRT INSTAN  
 100 0 30 0 0 0 0 0 0 0  
 JOPEL NHT LROPT TRACE  
 5 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED  
 NPLAN= 1 NRTIO= 4 LRTIO= 1  
 RTIOS= 1.00 .75 .50 .25

# SUB-AREA RUNOFF COMPUTATION

## 1 BASIN INFLOW HYDROGRAPH

ISTAG	ICOMP	IECON	ITAPE	JPLY	JPRT	INAME	ISTAGE	IAUTO
1	0	0	0	0	0	1	0	0

INVDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAPE	LOCAL
1	1	2.95	0.00	2.95	0.00	0.000	0	1	0

PRECIP DATA  
 SPEE PMS RL R12 R24 R48 R72 R96  
 0.00 22.00 112.00 123.00 133.00 141.00 0.00 0.00  
 TRSPC COMPUTED BY THE PROGRAM IS .800

LROPT	STPKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CHSTL	ALSKX	RTIMD
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.10	0.00	.10

UNIT HYDROGRAPH DATA  
 TP= 1.65 CP= .63 NTA= 0

RECESSION DATA  
 STOT2= -1.00 GRCSC= -10 RTIOR= 1.50  
 APPROXIMATE CLARY COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 3.93 AND P= 2.98 INTERVALS

UNIT HYDROGRAPH 12 END-OF-PERIOD ORIGINATES, LAG= 1.66 HOURS, CP= .63 VOL= 1.00  
 99. 351. 700. 419. 299. 213. 152. 108.  
 77. 55. 39. 28. 20. 14. 10. 7.

Sheet E021

MO-DA		MR-MN		PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW		MO-DA	MR-MN	PERIOD	RAIN	EXCS	LOSS	CORP 0	
1.01	1.30	1	.00	.00	.00	.00	3.	1.02	1.30	51	.06	.01	.05	17.			
1.01	1.00	2	.00	.00	.00	.00	3.	1.02	2.00	52	.06	.01	.05	26.			
1.01	1.30	3	.00	.00	.00	.00	3.	1.02	2.30	53	.06	.01	.05	33.			
1.01	2.00	4	.00	.00	.00	.00	3.	1.02	3.00	54	.06	.01	.05	39.			
1.01	2.30	5	.00	.00	.00	.00	3.	1.02	3.30	55	.06	.01	.05	43.			

END-OF-PERIOD FLOW									
MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO-DA	HR-MN	PERIOD
1-01	1-30	1	0.00	0.00	0.00	3.0	1-02	1-30	51
1-01	1-00	2	0.00	0.00	0.00	3.0	1-02	2-00	52
1-01	1-30	3	0.00	0.00	0.00	3.0	1-02	2-30	53
1-01	2-00	4	0.00	0.00	0.00	3.0	1-02	3-00	54
1-01	2-30	5	0.00	0.00	0.00	3.0	1-02	3-30	55
1-01	3-00	6	0.00	0.00	0.00	3.0	1-02	4-00	56
1-01	3-30	7	0.00	0.00	0.00	3.0	1-02	4-30	57
1-01	4-00	8	0.00	0.00	0.00	3.0	1-02	5-00	58
1-01	4-30	9	0.00	0.00	0.00	3.0	1-02	5-30	59
1-01	5-00	10	0.00	0.00	0.00	3.0	1-02	6-00	60
1-01	5-30	11	0.00	0.00	0.00	3.0	1-02	6-30	61
1-01	6-00	12	0.00	0.00	0.00	3.0	1-02	7-00	62
1-01	6-30	13	0.00	0.00	0.00	3.0	1-02	7-30	63
1-01	7-00	14	0.00	0.00	0.00	3.0	1-02	8-00	64
1-01	7-30	15	0.00	0.00	0.00	3.0	1-02	8-30	65
1-01	8-00	16	0.00	0.00	0.00	3.0	1-02	9-00	66
1-01	8-30	17	0.00	0.00	0.00	3.0	1-02	9-30	67
1-01	9-00	18	0.00	0.00	0.00	3.0	1-02	10-00	68
1-01	9-30	19	0.00	0.00	0.00	3.0	1-02	10-30	69
1-01	10-00	20	0.00	0.00	0.00	3.0	1-02	11-00	70
1-01	10-30	21	0.00	0.00	0.00	3.0	1-02	11-30	71
1-01	11-00	22	0.00	0.00	0.00	3.0	1-02	12-00	72
1-01	11-30	23	0.00	0.00	0.00	3.0	1-02	12-30	73
1-01	12-00	24	0.00	0.00	0.00	3.0	1-02	13-00	74
1-01	12-30	25	0.00	0.00	0.00	3.0	1-02	13-30	75
1-01	13-00	26	0.00	0.00	0.00	3.0	1-02	14-00	76
1-01	13-30	27	0.00	0.00	0.00	3.0	1-02	14-30	77
1-01	14-00	28	0.00	0.00	0.00	3.0	1-02	15-00	78
1-01	14-30	29	0.00	0.00	0.00	3.0	1-02	15-30	79
1-01	15-00	30	0.00	0.00	0.00	3.0	1-02	16-00	80
1-01	15-30	31	0.00	0.00	0.00	3.0	1-02	16-30	81
1-01	16-00	32	0.00	0.00	0.00	3.0	1-02	17-00	82
1-01	16-30	33	0.00	0.00	0.00	3.0	1-02	17-30	83
1-01	17-00	34	0.00	0.00	0.00	3.0	1-02	18-00	84
1-01	17-30	35	0.00	0.00	0.00	3.0	1-02	18-30	85
1-01	18-00	36	0.00	0.00	0.00	3.0	1-02	19-00	86
1-01	18-30	37	0.00	0.00	0.00	3.0	1-02	19-30	87
1-01	19-00	38	0.00	0.00	0.00	3.0	1-02	20-00	88
1-01	19-30	39	0.00	0.00	0.00	3.0	1-02	20-30	89
1-01	20-00	40	0.00	0.00	0.00	3.0	1-02	21-00	90
1-01	20-30	41	0.00	0.00	0.00	3.0	1-02	21-30	91
1-01	21-00	42	0.00	0.00	0.00	3.0	1-02	22-00	92
1-01	21-30	43	0.00	0.00	0.00	3.0	1-02	22-30	93
1-01	22-00	44	0.00	0.00	0.00	3.0	1-02	23-00	94
1-01	22-30	45	0.00	0.00	0.00	3.0	1-02	23-30	95
1-01	23-00	46	0.00	0.00	0.00	3.0	1-03	0-00	96
1-01	23-30	47	0.00	0.00	0.00	3.0	1-03	1-30	97
1-02	0-00	48	0.00	0.00	0.00	3.0	1-03	1-00	98
1-02	0-30	49	0.00	0.00	0.00	3.0	1-03	1-30	99
1-02	1-00	50	0.00	0.00	0.00	3.0	1-03	2-00	100

SUM 24.82 21.51 3.30 84050.  
( 630.1 ) ( 546.1 ) ( 24.1 ) ( 2381.16 )

6-HOUR 5217. 72-HOUR 838. TOTAL VOLUME 8395.

Sheet 9 of 21

CMS	227.	146.	49.	24.	2373.
INCHES	16.45	21.73	22.02	22.02	22.02
MM	417.83	551.91	559.29	559.29	559.29
AC-FT	2587.	3417.	3463.	3463.	3463.
THOUS CU M	3191.	4215.	4271.	4271.	4271.





Sheet 10 of 21

ST. 47. 116. 140. 168. 193. 202. 208.

211. 214. 237. 403. 665. 989. 1306. 1800. 1887. 2369.  
 3115. 3782. 4003. 3719. 3221. 2688. 2116. 1576. 1126. 840.  
 620. 463. 393. 378. 363. 348. 334. 321. 308. 296.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME

CFS 4003. 2608. 861. 419. 4187.

CMS 113. 74. 24. 12. 116.

INCHES 8.22 10.86 11.01 11.01

PM 208.91 275.95 279.65 279.65

AC-FT 1293. 1708. 1731. 1731.

THOUS CU M 1595. 2107. 2136. 2136.

HYDROGRAPH AT STA 1 FOR PLAN 1, RTIO 4

1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
6.	14.	21.	26.	28.	27.	23.	18.	14.	14.
10.	7.	4.	3.	3.	3.	3.	2.	2.	2.
4.	8.	10.	11.	11.	12.	12.	12.	13.	13.
15.	26.	40.	58.	73.	84.	92.	97.	101.	104.
106.	107.	129.	202.	332.	494.	653.	800.	944.	1184.
1557.	1891.	2001.	1859.	1611.	1344.	1058.	782.	573.	420.
310.	231.	197.	189.	181.	174.	167.	151.	154.	148.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME

CFS 2001. 1304. 431. 209. 2094.

CMS 57. 37. 12. 6. 593.

INCHES 4.11 5.43 5.50 5.50

PM 104.46 137.58 139.82 139.82

AC-FT 647. 854. 866. 866.

THOUS CU M 798. 1034. 1068. 1068.

\*\*\*\*\*

HYDROGRAPH ROUTING

2 ROUTE THROUGH LAKE

ISTAG ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUTO

0 0 0 0 0 0 0 0 0

ROUTING DATA

IPMP IPRT IPMP LSTR

0 0 0 0

MSIPS MSTOL LAS AMSK X TSK STORA ISPRAT

1 0 0 0.000 0.000 0.000 920. -1

STAGE 587.00 598.00 589.00 570.00 591.00 592.30 594.00 597.00

FLOW 0.00 18.00 50.80 97.50 174.20 309.70 529.70 1010.20

CAPACITY 920. 1370. 1822. 2469. 4003.

ELEVATION 587. 590. 592. 595. 600.

Sheet 11 of 21

CREL SPMTD COU EXPN ELEV COQL CAREA EXPL

587.0 0.0 C.0 0.0 0.0 0.0 0.0 0.0

TOPEL COOD EXPD BARRIO

\*\*\*\*\*



Sheet 13 of 21

1

\_\_\_\_\_

249



Q4(1)	Q4(2)	Q4(3)	ELNVT	ELMAX	RLNTH	SEL
.0350	.0170	.0350	568.0	600.0	1000.	.01200

CROSS SECTION COORDINATES--STA-ELEV--STA-ELEV--ETC
0+00 600.00 250.00 520.00 375.00 575.00
345.00 575.00 645.00 543.00 1395.00 600.00

	0.00	.64	1.31	2.02	2.77	3.28	12.62	24.84	41.32	61.07
STORAGE	54.07	110.34	129.65	172.63	208.65	247.94	293.48	336.28	365.33	437.66
OUTFLOW	0.00	337.21	1006.05	1985.02	2932.97	3646.96	8326.33	15160.03	26571.99	42338.60
	62944.34	89757.78	120192.05	157651.06	201528.62	252208.62	310365.56	375465.16	448765.03	530315.22
STAGE	568.09	569.68	571.37	573.05	574.74	576.42	578.11	579.79	581.47	583.16
	584.84	584.55	588.21	589.89	591.58	593.26	594.95	596.63	598.32	600.00
FLOW	0.00	337.21	1006.05	1985.02	2932.97	4646.96	8326.33	15160.03	26571.99	42338.60
	62944.34	89757.78	120192.05	157651.06	201528.62	252208.62	310365.56	375465.16	448765.03	530315.22

STATION 3, PLAN 1, RTIO 1

[illegible]

STOR

[illegible]

STAGE

	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2423	2424	2425	2426	2427	2428	2429	2430	2431	2432	2433	2434	2435	2436	2437	2438	2439	2440	2441	2442	2443	2444	2445	2446	2447	2448	2449	2450	2451	2452	2453	2454	2455	2456	2457	2458	2459	2460	2461	2462	2463	2464	2465	2466	2467	2468	2469	2470	2471	2472	2473	2474	2475	2476	2477	2478	2479	2480	2481	2482	2483	2484	2485	2486	2487	2488	2489	2490	2491	2492	2493	2494	2495	2496	2497	2498	2499	2500	2501	2502	2503	2504	2505	2506	2507	2508	2509	2510	2511	2512	2513	2514	2515	2516	2517	2518	2519	2520	2521	2522	2523	2524	2525	2526	2527	2528	2529	2530	2531	2532	2533	2534	2535	2536	2537	2538	2539	2540	2541	2542	2543	2544	2545	2546	2547	2548	2549	2550	2551	2552	2553	2554	2555	2556	2557	2558	2559	2560	2561	2562	2563	2564	2565	2566	2567	2568	2569	2570	2571	2572	2573	2574	2575	2576	2577	2578	2579	2580	2581	2582	2583	2584	2585	2586	2587	2588	2589	2590	2591	2592	2593	2594	2595	2596	2597	2598	2599	2600	2601	2602	2603	2604	2605	2606	2607	2608	2609	2610	2611	2612	2613	2614	2615	2616	2617	2618	2619	2620	2621	2622	2623	2624	2625	2626	2627	2628	2629	2630	2631	2632	2633	2634	2635	2636	2637	2638	2639	2640	2641	2642	2643	2644	2645	2646	2647	2648	2649	2650	2651	2652	2653	2654	2655	2656	2657	2658	2659	2660	2661	2662	2663	2664	2665	2666	2667	2668	2669	2670	2671	2672	2673	2674	2675	2676	2677	2678	2679	2680	2681	2682	2683	2684	2685	2686	2687	2688	2689	2690	2691	2692	2693	2694	2695	2696	2697	2698	2699	2700	2701	2702	2703	2704	2705	2706	2707	2708	2709	2710	2711	2712	2713	2714	2715	2716	2717	2718	2719	2720	2721	2722	2723	2724	2725	2726	2727	2728	2729	2730	2731	2732	2733	2734	2735	2736	2737	2738	2739	2740	2741	2742	2743	2744	2745	2746	2747	2748	2749	2750	2751	2752	2753	2754	2755	2756	2757	2758	2759	2760	2761	2762	2763	2764	2765	2766	2767	2768	2769	2770	2771	2772	2773	2774	2775	2776	2777	2778	2779	2780	2781	2782	2783	2784	2785	2786	2787	2788	2789	2790	2791	2792	2793	2794	2795	2796	2797	2798	2799	2800	2801	2802	2803	2804	2805	2806	2807	2808	2809	2810	2811	2812	2813	2814	2815	2816	2817	2818	2819	2820	2821	2822	2823	2824	2825	2826	2827	2828	2829	2830	2831	2832	2833	2834	2835	2836	2837	2838	2839	2840	2841	2842	2843	2844	2845	2846	2847	2848	2849	2850	2851	2852	2853	2854	2855	2856	2857	2858	2859	2860	2861	2862	2863	2864	2865	2866	2867	2868	2869	2870	2871	2872	2873	2874	2875	2876	2877	2878	2879	2880	2881	2882	2883	2884	2885	2886	2887	2888	2889	2890	2891	2892	2893	2894	2895	2896	2897	2898	2899	2900	2901	2902	2903	2904	2905	2906	2907	2908	2909	2910	2911	2912	2913	2914	2915	2916	2917	2918	2919	2920	2921	2922	2923	2924	2925	2926	2927	2928	2929	2930	2931	2932	2933	2934	2935	2936	2937	2938	2939	2940	2941	2942	2943	2944	2945	2946	2947	2948	2949	2950	2951	2952	2953	2954	2955	2956	2957	2958	2959	2960	2961	2962	2963	2964	2965	2966	2967	2968	2969	2970	2971	2972	2973	2974	2975	2976	2977	2978	2979	2980	2981	2982	2983	2984	2985	2986	2987	2988	2989	2990	2991	2992	2993	2994	2995	2996	2997	2998	2999	3000
--	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------

Sheet 16 of 21

MAXIMUM STORAGE = 3.

AC-FT	1214.	1513.	1516.	1516.
THOUS CU M	1498.	1866.	1869.	1869.

MAXIMUM STORAGE = 3.

MAXIMUM STAGE IS 575.2

STATION 3, PLAN 1, RTIO 3

**OUTFLOW**

Year	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2420	2421	2422	2423	2424	2425	2426	2427	2428	2429	2430	2431	2432	2433	2434	2435	2436	2437	2438	2439	2440	2441	2442
------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------

**STOR**

[illegible]

**STAGE**

[illegible]

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CBS	1497	1136	361	174	1735
CMS	42	32	10	5	493
PES		30.97	4.56	4.57	
PM		90.58	115.8	116.10	
-FT		503	717	719	
M		695	884	887	

MAXIMUM STORAGE = 2.

MAXIMUM STAGE IS 51.30VLS 52.25

STATION 3, PLAN 1, RTIO 4

4675200

[illegible]

Sheet 18 of 21





SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		587.00		587.00		592.30			
OUTFLOW		920.		920.		1822.			
		0.		0.		310.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF		TIME OF	
						MAX OUTFLOW		FAILURE	
						HOURS		HOURS	
1.00	595.86	3.56	2734.	5070.	10.00	43.00	43.00	0.00	0.00
.75	594.95	2.65	2457.	3401.	9.50	43.50	43.50	0.00	0.00
.50	592.67	1.37	2150.	1496.	8.50	44.00	44.00	0.00	0.00
.25	591.41	0.00	1648.	217.	0.00	46.00	46.00	0.00	0.00

PLAN 1 STATION 3

RATIO	MAXIMUM FLC-CFS	MAXIMUM STAGE-FT	TIME HOURS
1.00	5055.	574.6	43.00
.75	3436.	575.2	43.50
.50	1497.	572.3	44.00
.25	217.	569.1	46.50

STABILITY ANALYSIS

APPENDIX E

# TAMS

Job No. 1579-13

Sheet 1 of 24

Project NYS Dam Inspection

Date 5-27-81

Subject Kirk Lake Dam Stability Analysis

By JF

Ch'k. by \_\_\_\_\_

## Assumptions

- 1) The Unit weights assumed were as follows:  
Fill 125 pcf, Concrete 150 pcf, Earthfill (d.s.d) 65 pcf
- 2) Stability and conditions determined in accordance with Corps of Engineers Prime I Guidelines
- 3) The Concrete slab on the approach channel is not considered an integral part of the structure. The earthfill below the slab is considered to be completely pervious and saturated. Therefore total hydrostatic head is considered to be acting at the base of the structure.
- 4) Angle of internal resistance of Till Soil foundation is considered to be  $35^\circ$ ,  $C = 200$  pcf based on observations and engineering judgement.  $K_a$  assumed for backfill, based on  $\phi = 35^\circ$ .
- 5) Dam site is in Seismic Zone 2.
- 6) Ice Load of  $5K/ft^2$  acting at 1/2 ft from the top of the spillway section.

## Loading Conditions

- I) Normal Load; Lake at spillway crest, Elev. 587.  
No Ice Load.
- II) Normal Load; Lake at spillway crest; Elev 587.  
With Ice Load
- III) Unusual Load; Lake at 1/2 PMF Elev. 593.67
- IV) Extreme Load; Lake at PMF Elev. 595.86
- V) Unusual Load; Lake at Elev. 587 with  
addition of 0.05g earthquake force.

# TAMS

Job No. 1579-12

Sheet 2 of 24

Project NYS Dam Insp.

Date 5-27-01

Subject Kirk Lake Dam

By IF

Ch'k. by \_\_\_\_\_

## STABILITY CRITERIA (see assumption # 2)

a) Overturning Criteria Loading Cases ~~I, II, III~~ IV, V, VI - Resultant must fall within the middle 1/3 of the base.

- Loading Case IV Resultant must fall within the base

b) Sliding Criteria - Cases I through VI

Shear friction factor of safety  $\geq 3$   
(SFFS)

Case I

Shear friction factor of safety  $\geq 1.5$   
(SFFS)

# TAMS

Job No. 1579-13

Sheet 3 of 27


Project NYS DAM INSP

Date \_\_\_\_\_

Subject KICK LAKE DAM

By \_\_\_\_\_

Ch'k. by \_\_\_\_\_



# TAMS

Joh No. 1577-13

Project NYS DAM INSPECTION


Subject KIRK LAKE DAM

Sheet 4 of 20

Date 6-9-81

By JW

Ch'k. by \_\_\_\_\_



# TAMS

Job No. 1577-13

Sheet 5 of 24

Project 1075 Pine Street

Date 6-8-37


Subject 1. K. Lake - Spillway Analysis

By JW

Ch'k. by

*Calculate total Mass of Spilling Section*

*Section E-B- width 4 feet*



Total Mass of  $17' \times 22' \times 4.0'$  block =  $17' \times 22' \times 165 \text{ pcf} = 646,340 \text{ K}$   
 Less Mass of Channel below  $4' \times 6' \times 12.0' \times 165 \text{ pcf}$  =  $-75,240 \text{ K}$   
 Mass of (A)  $3' \times 4' \times 4.0' \times 165 \text{ pcf}$  =  $-7,720$   
 Mass of (B)  $2' \times 1' \times 4.0' \times 165 \text{ pcf}$  =  $-1,320$   
 (C)  $2' \times 4' \times 4' \times 165 \text{ pcf}$  =  $-26,400$   
 (D)  $2' \times 6' \times 4' \times 165 \text{ pcf}$  =  $-2,970$   
 (E)  $3' \times 3' \times 4' \times 165 \text{ pcf}$  =  $-1,155$   
 (F)  $1/2 (3' \times 5') \times 4' \times 165 \text{ pcf}$  =  $-495$   
 (G)  $1/2 (3' \times 5') \times 4' \times 165 \text{ pcf}$  =  $-1,155$

*17' x 22' x 4.0'*

*117.22'*



# TAMS

Job No. 1579-B

Sheet 6 of 24

Project 1415 Road Improvement

Date 6-9-51

Subject Kuck Lake Dam - Secondary Dam

By gus

Ch'k. by \_\_\_\_\_

Find Curved Surface Section B-B - symetric about long axis


Given: Area of Section B-B = 12.54 sq. ft. Height of Section B-B = 7.07 ft. Area of Section B-B = 12.54 sq. ft.

$$\begin{aligned} 24.540 \\ - 11.700 \\ \hline 12.840 \quad \times 1.5 = 64.86 \\ 12.840 \times 1.5 = 64.86 \\ 12.840 \times 1.5 = 64.86 \\ 12.840 \times 1.5 = 64.86 \\ 12.840 \times 1.5 = 64.86 \\ 12.840 \times 1.5 = 64.86 \end{aligned}$$

$$13.70 \times 1.5 = 20.55$$

$$12.84 \times 1.5 = 19.26$$

Section C-C 21.14



$$\begin{aligned} 1. \text{ Area of } 17.0 \times 1.5 &= 25.5 \\ 2. \text{ Area of } 17.0 \times 1.5 &= 25.5 \\ 3. \text{ Area of } 17.0 \times 1.5 &= 25.5 \\ 4. \text{ Area of } 17.0 \times 1.5 &= 25.5 \\ 5. \text{ Area of } 17.0 \times 1.5 &= 25.5 \\ 6. \text{ Area of } 17.0 \times 1.5 &= 25.5 \end{aligned}$$

$$\begin{aligned} 11.28 \times 1.5 &= 16.92 \\ 11.28 \times 1.5 &= 16.92 \\ 11.28 \times 1.5 &= 16.92 \end{aligned}$$

# TAMS

Job No. 1579-13

Sheet 7 of 24

Project 1976 Low Income

Date 6-5-51

**Subject** 1st Laban - 2nd - Bengali

By \_\_\_\_\_

Ch'k. by \_\_\_\_\_

Depth of Runway Mark - 67' on road S.W.

Total Area  $243' \times 17' \times 2(1') \times 100\text{sf} = 913.364 \text{ Kfz}$


Henry, agent of Edgar & Co.

From the above we deduce that the following

11/29/2011

4000 10000 20000 30000 40000 50000 60000 70000 80000 90000 100000

Miss Turner & Elizabeth



1990

$$A = \frac{1}{16} \ln \left[ \frac{2 + \sqrt{2}}{2 - \sqrt{2}} \right] = \frac{1}{16} \ln \left[ \frac{2 + 1.414}{2 - 1.414} \right] = \frac{1}{16} \ln \left[ \frac{3.414}{0.586} \right] = \frac{1}{16} \ln 5.824 = \frac{1}{16} (1.762) = 0.1101$$

Rechnung: 17.11.1903

1944-1945

7/3, 2002 - 1/2, 2007 - 65, 95.

754.185 2.45

the Center of the world of the

$$\frac{734.153 \text{ K}}{2} = \left( 245 + (3.14 \times 10^5) \right) \times (91.72) (54.153)$$

377.077 52.727 X - 32.84X

377.017 46.311 X

4-504'

17-531: 5.25'

# TAMS

Job No. 1579-12

Sheet 8 of 24

Project 145 Dr. ...

Date 6-2-71

Subject Railroad ...


By J. W.

Ch'k. by

Average Mass / ft of spillway width

$$\frac{\sum M_{avg}}{w} = \frac{117.2 + 166.2 + 754.1}{20.5'} = 50.6 \text{ Kips/ft}$$

Location of Net Resultant



$$\sum M = (754.1 \times 8.36) + (166.2 \times 9.6) + (117.2 \times 17.34) = 9214.8 \text{ K-ft}$$

Equival. Moment Arm  $\frac{M}{F} = \frac{9214.8}{1037.5 \text{ K}} = 8.88'$

Resultant M  $M = 449.3 \text{ K-ft}$

# TAMS

Job No. 1577-13

Sheet 9 of 24

Project M/S Dam Inspection

Date 6-2-51

Subject Kirk Lake Dam - Foundation Investigation

By JW

Ch'k. by \_\_\_\_\_


Calculate

ACTIVE EARTH PRESSURE ON WALL

- 1) Consider Concrete Slab as a 300 psf surcharge
- 2) Neglect pressure of lower level 25' pipe at center

$$\gamma_{\text{sat}} = 65 \text{ pcf} \quad K_a \text{ from } \phi = 35^\circ$$

$$K_a = .27$$



$$P_h = .5(300) + .27(65 \text{ pcf})(h)$$

$$P_h = 150 \quad P_h = 150 + 298 = 448 \text{ psf}$$

$$P = \frac{150 + 448}{2} \times 17 = 5,083 \text{ K}$$

Find Resultant Location ( $\frac{1}{2}$  Load  $P_h$ )

$$\text{from Top } 150 + \frac{1}{2}(17.55 \times 2) = \frac{5,083}{2}$$

$$150 + 8.775x^2 = 2541.5$$

$$x^2 + 17.1x - 287.6 = 0$$

$$x = 10.5$$

$$M_A = 17 \cdot 10.5 = 178.5'$$

$$F_H = 5,083 \text{ K}$$

$$M_D = 33.04 \text{ Kft}$$

# TAMS

Job No. 1579-13

Sheet 10 of 24

Project NYS Dam Inspection


Date 6-8-87

Subject Kirk Lake Dam - Seepage Analysis

By Jed

Ch'k. by \_\_\_\_\_

Calculate Side Shear Available at face of seepage section



From Previous Disturbance  
 Seepage Section  
 at 0.592.3 w/ Dam Seepage  
 is 0.592.3 pcf  $k_o = 1 - \sin \phi = 0.43$   
 Assume to irregular distribution

$$p = k_o \gamma_h = .43(62.6)h$$

$$P_i = \frac{1}{2} k_o \gamma_h L^2 =$$

$$h = 24.3 \quad P_i = 7.95 \text{ kips}$$

$$P_i = 7.95 \text{ kips} \times 15.5 = 123.2 \text{ kips}$$

$$Barris = 2 \times 123.2 = 246.4 \text{ kips}$$

Distributed pressure width of Seepage

$$P_H = \frac{246.4 \text{ kips}}{15.5 \text{ ft}} = 15.9 \text{ kips/ft}$$

Spillage Seepage is assumed

$$= 15 \times .43 \times 24.3 = 376.5 \text{ kips}$$

$$@ 1/2 \text{ ft} \times \frac{24.3}{2} = 8.1 \text{ ft}$$

$$\text{Average length} = \frac{376.5}{24.3} = 15.5'$$

$$\text{Friction factor} = \frac{1}{2} \tan \phi = \frac{1}{2} (1.35) = .46$$

$$\text{Upward resistance} .46 P_H = F_H = 7.31 \text{ kips}$$

$$\text{Resistance} M_H = 59.24 \text{ kft}$$

# TAMS

Job No. 1579-13

Sheet 11 of 24

Project KYS DI

Date 6-8-81


Subject KLD - SA

By [Signature]

Ch'k. by                     

## Circle I Hydrostatic Pressure WLO 587'

- 1)  $H_2O$  pressure acts on 15.5' width of Spilling nose pressure on 24' turning wall -



## Circle II Ice Force Calculations

1' thick ice cap at Water Level bearing 5000 psf

$$F_h = 5000 \text{ psf} \times 9$$

$$M_h = 18.5'$$

$$M = 18.5 \times 5000 \times 9 = 92.5 \text{ kft}$$

# TAMS

Job No. 1579-13

Sheet 12 of 24

Project NYS DE

Date 6-20-81

Subject KLD-SA



By JW

Ch'k. by \_\_\_\_\_

Case III  $\frac{1}{2}$  PMF WL@ 593.67

Face of Dam Upstream


WL 593.67



Zone A

$$F_H = 19.88 \text{ k} \quad F_V = 13.6 \text{ k}$$

$$X_H = 7.2' \quad X_V = 11.3'$$



Zone B

$$F_H = 19.16 \text{ k} \quad F_V = 12.6 \text{ k}$$

$$X_H = 6.9' \quad X_V = 11.3'$$

# TAMS

Job No. 1579-13

Sheet 13 of 24

Project 145 Dam Inspection


Date 6-8-01

Subject Kirk Lake Dam Spilling the Face

By JW

Ch'k. by \_\_\_\_\_

Crack III Cont.



Calculate Ave Force / unit width of face / Moment Arm

Force	Distance	F <sub>H</sub>	X <sub>H</sub>	F <sub>u</sub>	M
1	1.1	19.35	1.6	27.83	200.37
2	7.0	19.16	6.9	134.10	925.29
3	7.1	20.14	7.3	142.99	1043.80
				304.92	2169.46

For 15.5 ft width  $\bar{F} = 19.67 \text{ kips}$

$\bar{M}_H = \frac{2169.46}{304.92} = 7.11'$

$\bar{F}_H = 19.67 \text{ kips}$   $\bar{M}_H = 139.9 \text{ k-ft}$

$\bar{F}_u = 13.6 \text{ kips}$   $\bar{M}_u = 153.68 \text{ k-ft}$



# TAMS

Job No. 1572-13

Sheet 14 of 24

Project 1145 Long Exposure

Date 8/31

Subject Kirk Lake Dam - Topography


By J. J. J.

Ch'k. by \_\_\_\_\_

Case II PMP 100.0 595.86

Same face of Dam as Case III

Zone A  $\pm 0.15.86$



$P = 100.0 \times 428 = 42800$

$T = \frac{42800}{2} = 22.7$

$2 \times 11.8 = 23.6$

$x = 7.6$

$F = 100.0 \times 11.8 = 1180$

$x = 11.8$

$T = 22.7$

$M = 172.5$

$T = 14.8$

$M = 167.2$

# TAMS

Job No. 1579-13

Sheet 15 of 24

Project 1943 Pine Ridge

Date 6-2-31


Subject Peak Lake Dam - Cross Section

By JW

Ch'k. by \_\_\_\_\_

Panel B

$\frac{1}{2} \times 595.86$



$$P_1 = (595.86 - 553) \cdot 62.4 = 553$$

$$P_2 = 1738 \text{ as given}$$

$$P_H = \frac{553 + 1738}{2} \cdot 9 = 21.8 \text{ Kips}$$

$$\bar{x} = 1738 \times \frac{1}{2} \cdot 62.4^2 = 10,882 = 0$$

$$\bar{x} = 7.2$$

$$T_H = 21.8 \text{ Kips } \bar{x} = 7.2'$$


$$M_H = 157.0 \text{ K-ft}$$

$$T_V = 14.8 \text{ Kips}$$

$$M_V = 167.2 \text{ K-ft}$$

Panel C

$\frac{1}{2} \times 595.86$



$$P_1 = (595.86 - 366) \cdot 62.4 = 366$$

$$P_2 = 1738 \text{ as given}$$

$$P_H = \frac{366 + 1738}{2} \cdot 9 = 23.14 \text{ Kips}$$

$$\bar{x} = 1738 \times \frac{1}{2} \cdot 62.4^2 = 11,572 = 0$$

$$\bar{x} = 7.7'$$

$$T_H = 23.14 \text{ Kips } \bar{x} = 7.7'$$

$$M_H = 179.2 \text{ K-ft}$$

$$T_V = 14.8 \text{ Kips } \bar{x} = 11.3'$$

$$M_V = 167.2 \text{ K-ft}$$

# TAMS

Job No. 1577-13

Sheet 16 of 24

Project 1975 Dam Inspection

Date 6-8-71

Subject Kink Lake Dam - Stability Analysis

By JW

Ch'k. by \_\_\_\_\_

Calculate Ave. Force / unit width + resultant moment

<u>Point</u>	<u>Depth</u>	<u>F<sub>H</sub></u>	<u>X<sub>H</sub></u>	<u>F<sub>V</sub></u>	<u>M<sub>0</sub></u>
A	1.4'	22.7K	7.6'	31.8K	241.5 K-ft
B	7.0'	21.8K	7.2'	152.6K	1098.7 K-ft
C	7.1'	23.14K	7.7'	164.3K	1235.1 K-ft
				348.7K	2075.3 K-ft

$$\bar{F}_H = \frac{348.7}{15.5} = 22.5 \text{ K}$$

$$\bar{M}_0 = \frac{2075.3}{15.5} = 133.9 \text{ K-ft}$$

$$\bar{F}_H = 22.5 \text{ K} \quad \bar{M}_0 = 133.9 \text{ K-ft}$$

$$\bar{F}_H = 21.8 \text{ K} \quad \bar{M}_0 = 167.2 \text{ K-ft}$$

# TAMS

Job No. 1571-13

Sheet 17 of 24

Project M/S Dam Inspection

Date 6-8-81

Subject Kirk Lake Dam

By Jed

Ch'k. by

Calculate Y-Y Centroid of mass for location of dynamic mass sources  
Find Center of mass  $\rightarrow$  in Y-Y direction for Spillway section

Section E-B from pg 5

Total Mass 117.206 Kips

$$M_{\text{top}} = 4 \times 6 \times 3 \times 1.65 = 11.88$$

From Top

$$0-3' \text{ Mass } (3.5 \times 4 \times 1.65) - M_{\text{top}} - M_{\text{top}} = 21.7 - 7.92 - 1.92 = 11.88$$

$$3-4' \text{ Mass } ((4-3) \times 15 + 4 \times 1.65) - (4 \times 6 \times (4-3) \times 1.65)$$

$$\text{from } \frac{1}{2} \text{ total mass} = \frac{117.206}{2} = 58.603$$

$$58.603 = 7.92 + (Y-3)(11) - (Y-3)(5.7)$$

$$58.603 = 7.92 + 5.4(Y-3)$$

$$50.683 = 5.4(Y-3)$$

$$Y-3 = 9.38$$

$$X = 11.53' \text{ from Top of spill}$$

Section C-C

Mass of 6' Total mass = 16.12 Kips find the height

from top

$$0-3' \text{ Mass } (2.15 \times 3.1 \times 1.65) - M_{\text{top}} - M_{\text{top}} = 11.02 - 6.138 - 1.92 = 15.34$$

$$3-4' \text{ Mass } (Y-3)(15)(3.1) \times 1.65$$

$$\frac{1}{2} \text{ Total Mass} = 8.06 \text{ find Centroid}$$

$$8.06 = 15.34 + (Y-3)2.67$$

$$6.76 = (Y-3)2.67$$

$$2.53 = Y-3$$

$$Y = 11.83' \text{ from top}$$

# TAMS

Job No. 1579-13

Sheet 18 of 24

Project Nile Dam - 1954

Date 6-8-81

Subject Kirk Lake Dam

By Jed

Ch'k. by \_\_\_\_\_

Find Centroid of Remaining Mass as per pg. 7  
Total mass is 754.153

$$Mass \times Y = 53 = [15 \times 2(6.7) \times .165] (Y) - 103.257 -$$

Prof. mass =


$$377.077 = 33.165Y - 103.257$$

$$480.334 = 33.165Y$$

$$Y = 14.48' \text{ from top of wall}$$

Recall mass of remaining mass is 1037.5 k  
Mass is by sum of mass of remaining mass

Area	Mass
117.206	22-11.53 = 10.47'
166.2	22-11.53 = 10.47'
754.153	243-14.5 = 9.82



$$\sum Mo = 7405.8 + 1699.2 + 10.47' = 10,323.2 \text{ kft}$$

$$\text{Total Mass} = 1037.5 \text{ k}$$

$$\frac{\sum Mo}{\text{Total Mass}} = \frac{10,323.2 \text{ kft}}{1037.5 \text{ k}} = 9.95'$$

Location of Y-Y Center is 9.95' from base as  
indicated by center line.

# TAMS

Job No. 1579-13

Sheet 19 of 24

Project 1145 Dam Inspection

Date 6-2-81

Subject Kick Lake Dam - Steady State Seepage

By gmd

Ch'k. by \_\_\_\_\_

CASE II, Normal Loading Plus Earthquake  
Zone 2  $\Rightarrow 0.05g$

1) HYDRODYNAMIC LOAD - 3' of Freewater

Zangars Method

for Vertical wall  $\Theta = 0$   $C = 0.73$

$$P = 0.73 \times 0.05 \times 0.0624 \times 3.0 = .0068$$

$$P_T = \frac{1}{2} (.0068) 3 = .010 \text{ kips}$$

$$M = .010 \times .4 \times 3 = .012 \text{ k-ft}$$

2) Dynamic Load

Soil Masses

$$W_s = 125 \left( \frac{1}{2} \right) (17)^2 (1.75) (0.05) = .677 \text{ Ksf}$$

Apply at  $\frac{2}{3}$  wall Ht

see case

(Sechrest 1970)

$$M = .677 \times 17 \times \frac{2}{3} = 7.68 \text{ k-ft}$$

Masses (inertia)

for 0.05g  $\Sigma F = 50.6 \text{ kips}$

for 0.05g  $\Sigma F = 50.6 \times 0.05 = 2.53 \text{ kips}$

$$M_a = 9.95' \quad M = 25.17 \text{ k-ft}$$

$$\Sigma F_c = 3.20 \text{ kips}$$

$$\Sigma M = 32.85 \text{ k-ft}$$

# TAMS

Job No. 1579-P3

Sheet 20 of 24

Project NY 5 Pm Temporary

Date 3-12-51

Subject Kick Out Line - Stability Analysis

By EW

Ch'k. by \_\_\_\_\_

Analysis

Case I Normal Loading

	<u><math>F_v</math></u>	<u><math>F_H</math></u>	<u><math>M_R</math></u>	<u><math>M_D</math></u>
Dry Load	50.6	—	449.3 kft	—
Side Shock	—	-7.31	39.2	—
Hydrostatic Load	-11.3	11.26k	—	185.2 kft
Earth Forces	—	5.1k	—	33.0 kft
	37.3	9.05	508.5	218.2

$$\Sigma M = 508.5 - 218.2 = 290.3 \text{ kft}$$

$$\bar{e} = \frac{17}{2} - \frac{290.3}{37.3} = 1.11'$$

is  $\frac{17}{6} - 1.11 \geq 0$  (1.72 ft) Result within middle  
 $\checkmark$  - OK

Sliding Stability required  $\checkmark$  assume  $C \approx 20\%$

$$F.S. = \frac{F_v + C}{F_H}$$

$$F.S. = \frac{37.3 + 0.2(50.6)}{9.05} = 3.41 \quad \text{OK}$$

# TAMS

Job No. 1579-13

Sheet 21 of 24

Project 1945 Univ. Temp. 1941

Date 6-10-81

Subject Klein Lake Land - 5700 ft. 1941

By J.F.U.

Ch'k. by \_\_\_\_\_

## Case II ICE loading of Normal water load

	<u>I<sub>1</sub></u>	<u>E<sub>1</sub></u>	<u>M<sub>12</sub></u>	<u>M<sub>10</sub></u>
Demo Load	50.6		449.3	
Side Shear	-	-7.31	57.2	
Hydrostatic Load	-11.3	11.26	-	185.2
ICE Load	-	5.0	-	92.5
Earth Pressure	-	5.1	-	33.0
	<u>39.3</u>	<u>14.05</u>	<u>506.5</u>	<u>310.7</u>

$$S.H. = 506.5 - 310.7 = 197.8 \text{ kft}$$

$$e = \frac{17}{2} - \frac{197.8}{39.3} = 3.46'$$

$$12 \frac{17}{6} - 3.46 \geq 0 \quad (-.63) \text{ in.} \quad \text{Total Height of water load is } 17'$$

sliding capacity  $\phi' 35^\circ$   $c' = 200 \text{ psf}$   $\mu = 0.30$

$$F.S. = \frac{39.3 + 10 - 17(0.3)}{14.05} = \underline{2.20}$$

At this time, the water level is high and the sliding capacity is within the acceptable criteria.



# TAMS

Job No. 1579-13

Sheet 22 of 24

Project NYS Dam Inspection

Date 6-20-31

Subject Kirk Lake Dam - Seepage Analysis

By J. E. J.

Ch'k. by \_\_\_\_\_

Case III  $\frac{1}{2}$  PMF - NO ICE.

	<u>F<sub>v</sub></u>	<u>F<sub>u</sub></u>	<u>M<sub>v</sub></u>	<u>M<sub>u</sub></u>
Dead Load	20.6		449.3	
Side Sluice	—	-7.31	37.2	
Hydrostatic Load	-12.6	19.67	—	293.58
Earth Pressure	—	5.10	—	32.0
	<u>37.0</u>	<u>17.46</u>	<u>508.5</u>	<u>326.58</u>

$$\Sigma M = 508.5 - 326.58 = 181.92 \text{ Kft}$$

$$\bar{e} = \frac{17}{2} - \frac{181.92}{37.0} = 3.58'$$

15'  $\frac{17}{6} \cdot 3.58 = 10.747$  NO INST. ACCEPTABLE - TOO NEAR  
NOT A TAIL W. TAIL  $\frac{1}{3}$  OF 15' -

Sliding Stability assumed  $\phi = 35^\circ$   $C = 200 \text{ p.s.f.}$

$$F.S. = \frac{37.0 (\tan 35^\circ + 17.46)}{17.46} = 1.68 < 3$$

Does not resist sliding

# TAMS

Job No. 1577-13

Sheet 23 of 24

Project 1945 Dam Construction

Date 1-20-51

Subject Kuck Lake Dam - secondary design

By J. H. H.

Ch'k. by \_\_\_\_\_

## Case IV PMF

	<u><math>F_u</math></u>	<u><math>F_d</math></u>	<u><math>W_u</math></u>	<u><math>W_d</math></u>
Dam Load	58.6	—	449.3	—
Stem Shear	—	-7.31	57.2	—
Hydrostatic Load	-14.8	22.50	—	336.3
Earthquake	—	5.10	—	33.2
	<u>35.8</u>	<u>20.29</u>	<u>508.5</u>	<u>369.5</u>

$$\Sigma H = 508.5 - 369.5 = 140.2 \text{ k ft}$$

$$Z = \frac{17}{2} - \frac{140.2}{35.8} = 4.58$$

$$15 \quad \frac{17}{6} - 4.58 \geq 0 \quad (-1.75 \text{ no}) \quad \text{middle } 1/3 \text{ of } \frac{17}{6} \text{ is } 4.58$$

Sliding Force Diagram

$\phi = 35^\circ$   $C = 200 \text{ psf}$  at base

$$F.S. = \frac{369.5}{20.29} = 18.21$$

Does not meet criteria

## Case II - Dynamic Loading

	<u><math>F_u</math></u>	<u><math>F_d</math></u>	<u><math>W_u</math></u>	<u><math>W_d</math></u>
Dam Load	58.6	—	449.3	—
Stem Shear	—	-7.31	57.2	—
Hydrostatic Load	-11.3	11.26	—	155.2
Earthquake	—	5.10	—	33.2
Dynamic Load	—	3.20	—	32.85
Hydrodynamic Load	—	1.01	—	1.01
	<u>39.3</u>	<u>12.26</u>	<u>508.5</u>	<u>251.06</u>

$$\Sigma H = 508.5 - 251.06 = 257.44$$

$$Z = \frac{17}{2} - \frac{257.44}{39.3} = 1.95$$

$$15 \quad \frac{17}{4} - 1.95 \geq 0 \quad (2.30 \text{ psf})$$

Sliding Force Diagram

$\phi = 35^\circ$   $C = 200 \text{ psf}$  at base

AD-A107 408

TIPPETT-ABBETT-MCCARTHY-STRATTON NEW YORK  
NATIONAL DAM SAFETY PROGRAM. KIRK LAKE DAM (INVENTORY NUMBER N.--ETC(U)  
AUG 81 E O'BRIEN

F/G 13/13

DACW51-81-C-0008


NL .

UNCLASSIFIED

2 1 1 1  
A 1 1 1 1



END  
DATE  
FILMED  
12-81  
DTIC



# TAMS

Job No. 1579-13

Sheet 24 of 24

Project 1145 Dam Improvement

Date 6-10-81

Subject Kirk Lake Dam - Stability Analysis

By JFW

Ch'k. by \_\_\_\_\_

## SUMMARY

Case	Resultant Location		Stability	
	<u>E</u>	<u>Accurate</u>	<u>Sliding F.S.</u>	<u>Accurate</u>
<u>I</u>	1.11'	yes	3.41 > 3	yes
<u>II</u>	3.46'	NO	2.20 < 3	NO
<u>III</u>	3.58'	NO	1.68 < 3	NO
<u>IV</u>	4.58'	NO	1.40 < 3	NO
<u>V</u>	2.30'	yes	2.52 > 1.5	yes

REFERENCES

APPENDIX F

#### REFERENCES

1. "Flood Hydrograph Package (HEC-1) Users Manual for Dam Safety Investigations", U. S. Army Corps of Engineers, Hydrologic Engineering Center, September 1979.
2. "Seasonal Variation of the Probable Maximum Precipitation, East of the 105th Meridian for Areas from 10 to 1,000 Square Miles, and Durations of 6, 12, 24 and 48 Hours", Hydrometeorological Report No. 33. Weather Bureau, U.S. Department of Commerce, April 1956.
3. "Recommended Guidelines for Safety Inspection of Dams", Department of the Army, Office of the Chief of Engineers, Appendix B.
4. The University of the State of New York, The State Education Department State Museum and Science Service Geological Survey - MAP and Chart Series No. 5, Geologic MAP of New York 1961, Lower Hudson Sheet.

OTHER DATA

APPENDIX G



THE CITY OF NEW YORK  
DEPARTMENT OF  
WATER SUPPLY, GAS AND ELECTRICITY

BUREAU OF WATER SUPPLY  
MUNICIPAL BUILDING  
NEW YORK

Structures impounding  
water

February 28, 1925.

Mr. Roy G. Finch,  
State Engineer,  
Albany, New York.

Dear Sir:

Your favor of the 19th inst. acknowledging receipt of our letter of February 13, 1925 with accompanying reports on fourteen dams in the Croton watershed, to hand.

I am transmitting herewith reports on six distributing reservoirs (Croton and Long Island supplies) within the limits of the City of New York, one distributing reservoir (Hill View Catskill supply) just north of the city limits and one storage reservoir (Hempstead) on Long Island.

Your assumption that the Muscoot dam (your number 406) is just below the point where the Muscoot river originally flowed into the Croton River, is correct.

421 LX { I note your reference to the dam on the headwaters of the Muscoot river one mile from the village of Mahopac and 1/4 mile above the NYC RR bridge. This dam is undoubtedly the one at the outlet of Kirk Lake and is located one half mile above the village of Mahopac Falls. It is owned by the City of New York and was originally constructed in 1870-71; it was reconstructed in 1881. Length of dam 160 feet; 36" inlet pipe 19 feet below high water. There are no plans of this dam in existence so far as we have know.

Very truly yours,

*Wm. H. Hall*  
Chief Engineer

Enc. 8 reports

✓  
54 L H New General Post Office  
102 " High Bridge  
135 " Kirk Lake  
136 " Mahopac Falls  
160 " Hill View

481 L H

1181 18  
NEW YORK CITY  
118 WEST 40th STREET  
TELEPHONE CO.

CARMEL, N. Y., COURIER (662)

Friday, January 26, 1917.

so last the 1885  
Temperance, in whose interest he was  
working had transferred a number  
of their men, to the eastern states.

#### A LEAK IN KIRK-LAKE DAM

A small leak was discovered in the dam at Kirk Lake on last Friday evening which required about three hours work to repair it. It was fortunate that the leak was discovered in time or perhaps the dam might have given away causing much trouble.

#### THIRD ANNUAL RECEPTION

The third annual reception and ball

## NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

DAM INSPECTION REPORT  
(By Visual Inspection)

Dam Number	River Basin	Town	County	Hazard Class*	Date & Inspector
781	L. Hudson	Connetquot	Peterson	B-C	12/22/76 KAH

Type of Construction	Use
<input type="checkbox"/> Earth w/concrete spillway	<input type="checkbox"/> Water Supply
<input type="checkbox"/> Earth w/drop inlet pipe	<input type="checkbox"/> Power
<input checked="" type="checkbox"/> Earth w/stone on <del>spillway</del> spillway	<input checked="" type="checkbox"/> Recreation
<input type="checkbox"/> Concrete	<input type="checkbox"/> Fish and Wildlife
<input type="checkbox"/> Stone	<input type="checkbox"/> Farm Pond
<input type="checkbox"/> Timber	<input type="checkbox"/> No Apparent Use-Abandoned

Estimated Impoundment Size	Estimated Height of Dam above Streambed
<input type="checkbox"/> 1-5 acres	<input type="checkbox"/> Under 10 feet
<input type="checkbox"/> 5-10 acres	<input type="checkbox"/> 10-25 feet
<input checked="" type="checkbox"/> Over 10 acres 120 (+/-) ac. 565 MG	<input checked="" type="checkbox"/> Over 25 feet 30'

Condition of Spillway

<input checked="" type="checkbox"/> Service satisfactory	<input type="checkbox"/> Auxiliary satisfactory
<input type="checkbox"/> In need of repair or maintenance	<input type="checkbox"/> In need of repair or maintenance

Explain: \_\_\_\_\_

Condition of Non-Overflow Section

<input checked="" type="checkbox"/> Satisfactory	
<input type="checkbox"/> In need of repair or maintenance	Explain: _____


Condition of Mechanical Equipment

<input checked="" type="checkbox"/> Satisfactory	
<input type="checkbox"/> In need of repair or maintenance	Explain: _____

Evaluation (From Visual Inspection)

- ☒ No defects observed beyond normal maintenance
- ☐ Repairs required beyond normal maintenance

\*Explain Hazard Class, if Necessary \_\_\_\_\_



(NOTICE: After filling out one of these forms as completely as possible for each dam in your district, return it at once to the Conservation Commission, Albany.)

STATE OF NEW YORK  
CONSERVATION COMMISSION  
ALBANY

DAM REPORT

July 27th, 1915  
(Date)

CONSERVATION COMMISSION,

DIVISION OF INLAND WATERS.

GENTLEMEN:

I have the honor to make the following report in relation to the structure known as the Kirk Lake Dam.

This dam is situated upon the Headwaters of Muscoogee River  
in the Town of Cornel, Putnam County,  
about 1 mile from the Village ~~near~~ of Lake Mahopac.  
(State distance)  
The distance down stream from the dam, to the N.Y. Central R.R. Bridge,  
(Up or down) (Give name of nearest important stream or of a lake)  
is about 1/4 mile.  
(State distance)

The dam is now owned by New York City  
(Give name of owner)  
and was built in or about the year 1872, and was extensively repaired or reconstructed during the year \_\_\_\_\_.

As it now stands, the spillway portion of this dam is built of Cut Stone  
(State whether of masonry, concrete, or other material)  
and the other portions are built of Cut Stone Earth fill.  
(State whether of masonry, concrete, or other material, or whether of earth fill)

As nearly as I can learn, the character of the foundation ~~bed~~ under the spillway portion of the dam is Rock and under the remaining portions such foundation bed is Rock & Gravel.

213-C F

The total length of this dam is 150 feet. The spillway or waste-weir portion, is about 20 feet long, and the crest of the spillway is about 4 feet below the top of the dam.

The number, size and location of discharge pipes, waste pipes or gates which may be used for drawing off the water from behind the dam, are as follows: One 36"

discharge pipe directly under spillway  
State briefly, in the space below, whether, in your judgment, this dam is in good condition, or bad condition, describing particularly any leaks or cracks which you may have observed.)

This dam is in excellent condition and should it go out the water would pretty nearly take care of itself without serious damage to surrounding property because there seems to be scarcely any buildings in its valley and a special artificial sluiceway through the gulch has been built.



Reported by

L. D. Seymour  
(Signature)


(Address—Street and number, P. O. Box or R. F. D. route)

Walcott, N. Y.  
(Name of place)


(SEE OTHER SIDE)

(In the space below, make one sketch showing the form and dimensions of a cross section through the spillway or waste-weir of this dam, and a second sketch showing the same information for a cross section through the other portion of the dam. Show particularly the greatest height of the dam above the stream bed, its thickness at the top, and thickness at the bottom, as nearly as you can learn.)


SPILLWAY SECTION



OTHER SECTION



(In the space below, make a third sketch showing the general plan of the dam, and its approximate position in relation to buildings or other conspicuous objects in the vicinity.)



END

DATE  
FILMED

12-81

DTIC